

Cost Summary

A. Total Cost Breakdown

Cost Component	Amount (Ngn)	% Of Total
Excavation Cost	1,701,120	37.90%
Wall Casting Cost	1,021,500	22.80%
Water Supply Cost	514,000	11.50%
Labour Cost	744,500	16.60%
Base Casting Cost	506,250	11.30%
Total	4,487,370	100.00%

B. Cost By Location

Location	Labour	Excavation	Base Cast	Wall Cast	Water	Total
Site A	316,500	988,720	233,500	428,800	205,000	2,172,520
Site B	388,000	712,400	272,750	592,700	309,000	2,274,850
Road Section	40,000	0	0	0	0	40,000
Main Store	0	0	0	0	0	0
Total	744,500	1,701,120	506,250	1,021,500	514,000	4,487,370

C. Cost By Week

Week	Labour	Excavation	Base Cast	Wall Cast	Water	Weekly Total
W5	91,000	718,720	0	0	0	809,720
W6	25,000	224,700	0	0	0	249,700

W7	30,500	239,200	0	0	0	269,700
W8	110,000	32,000	177,000	64,000	77,000	460,000
W9	94,000	227,600	56,500	301,800	100,000	779,900
W10	116,000	194,400	166,000	183,000	119,000	778,400
W11	100,000	52,500	93,050	206,700	102,000	554,250
W12	24,000	0	0	47,900	21,000	92,900
W13	28,000	0	0	101,500	28,000	157,500
W14	68,000	12,000	13,700	110,600	59,000	263,300
W15	18,000	0	0	6,000	5,000	29,000
W16	28,000	0	0	0	0	28,000
W17	12,000	0	0	0	0	12,000
W18	0	0	0	0	3,000	3,000
Total	744,500	1,701,120	506,250	1,021,500	514,000	4,487,370

D. Unit Rates Applied

Item	Rate
Excavation – Site A (Weeks 5–9)	800 Ngn/M
Excavation – Site B (Weeks 10–18)	1,000 Ngn/M
Base Casting (All Locations)	500 Ngn/M
Wall Casting (All Locations)	1,000 Ngn/M
Water Supply	1,000 Ngn/Trip